BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2018-19/OW/WORK_INDENT34128

APPROVED SCHEDULE-B

EE/BTP/BBMP/E-PMT/19/2018-19, Date: 06.02.2019

Desilting and Repairs to SWD at Kodigehalli in ward No 08 Kodigehalli

Sl. No.	Approved Qty	Description	Unit	Approved Tender Rates of B Girish ( )	
				In Figures	In Words
1	2.34	KSRRB M200-12.2. Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts complete as per specifications. i) Lime /Cement Concrete. I. By Manual Means :B. Cement Concrete Grade M-15 & M-20. MORTH Specification No. 202. (P.No. 139, I.No. 18.18 of CSR 2018-19)	Cum	665.00	Rupees Six Hundred Sixty Five Only
2	445.00	KSRRB 300-1. Earthwork excavation by manual means in rodinary soil involving an average horizontal throw upto 2 m and an average lift upto 0.5m, excavated surafce levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking clods complete as per specifications.. Pg No.143.Item No.19.1)	Cum	241	Rupees Two Hundred Fourty one Only
3	28.43	KSRB 5.2-3: Providing and constructing granite size stone masonry in foundation cement mortar 1:6, stone hammered dressed in courses not less than 20cms high, bond stones at 2m apart in each course including cost of materials, labour, curing etc., complete as per specifications.(P-25. Item No. 5.6)	Cum	4628.00	Rupees Four Thousand six Hundred Twenty Eight Only
4	9.07	KSRB 4-1.6: Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240 kgs, with 20 mm and down size graded granite matel coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum, machine mixed, concrete laid in layers not eceeding 15 cms, thick, well compacted, in foundation and plinth including cost of all materials, labour, HOM of machinery curing complete as per specifications. (Page No. 13. Item No. 4.6)	Cum	5460.00	Rupees Five Thousand Four Hundred Sixty Only
5	156.00	Supplying and fixing M.S. Rectangular poles made out of 2 equal angles of 65x65x6 mm welded together and fixed in CC (1:2:4) WITH 2 NOS 16mm dia M.S. hold fast rods each of length 25 cms. Including cost of all materials cutting, bending scaffolding wherever necessary, nicely finishing the welded joints with all lead lifts and as per the directions of the Engineer-in - charge of the work and including providing 2 coats of approved quality paint over one coat of shop painting (excluding cost of earthwork and concrete) (Page No. 266. Item No. 37.2)	M	865.00	Rupees Eight Sixty Five Only
6	312.00	Providing chain link fencing 50mm size of 8 guage properly stretched between existing rectangular poles and fixed with suitable bolts & nuts, the free ends shall be welded to the pole and block pipe at top and bottom as required including cost of all materials, labour, lead and lifts and as per the directions of the Engineer-in-charge of work including two coats of approved quality paint over one coat of shop paint (Page No. 266. Item No. 37.3)	M	720.00	Rupees Seven Hundred Twenty Only

7	468.00	Providing and fixing M.S. Block pipe of 38mm dia, of heavy guage of 14 including removing the bends, cutting the pipe, and fixing pipe in between the existing two verticle poles (M.S. rectangular poles) and spot welding the chain link with M.S. block pipe including cost of all materials wastage in cutting, and scaffolding wherever necessary with all lead and lift as directed by the Engineer-in-charge of work etc., complete including two coats of approved quality paint over one coat of shop paint (Page No. 266. Item No. 37.4)	M	410.00	Rupees Four Hundred Ten Only

Signature of the Contractor

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92